



NOTE 1: CONTRACTOR TO BURY 2 RUNS OF 4" SCHEDULE 40 PVC 4 FEET DEEP TO BASE OF UTILITY POLE. STUB CONDUIT OUT AT GROUND LEVEL. INSTALL A PULL STING IN ONE RUN OF CONDUIT.

NOTE 2: REFERENCE UVG-LOCATION DRAWING FOR TRANSFORMER CLEARANCE FROM A STRUCTURE.



2000-2500 KVA
TRANSFORMER PAD DETAIL

DRAWN CLJ	CHECK JLJ	DATE 06-09-16	FILE NAME TRANS_PAD_DETAIL-D
SCALE NOT TO SCALE	SHEET 1 OF 1	ASSEMBLY	