


3000 PSI CONCRETE MIN

NOTE 1: CONTRACTOR TO BURY 2 RUNS OF 4" SCHEDULE 40 PVC 4 FEET DEEP TO BASE OF UTILITY POLE. STUB CONDUIT OUT AT GROUND LEVEL. INSTALL A PULL STING IN ONE RUN OF CONDUIT.

NOTE 2: REFERENCE UVG-LOCATION DRAWING FOR TRANSFORMER CLEARANCE FROM A STRUCTURE.

			
<b>750-1500 KVA TRANSFORMER PAD DETAIL</b>			
DRAWN CLJ	CHECK JLJ	DATE 07-25-16	FILE NAME TRANS_PAD_DETAIL-C
SCALE NOT TO SCALE	SHEET 1 OF 1	ASSEMBLY	